ROYALTY CALCULATION

Name of Work : Improvements of CC drain & Covering slab & Re-Asphalting excel kalyana Mantapa road and Bharathi theatre road in ward No 15 T.Dasarahalli

Plain Cement Concrete 1:3:6			
Description	Qty in Cum	Constant	Total Qty
Sand	90.42	0.46	41.59
Jelly	90.42	0.89	80.47
Cement Concrete M20			
Sand	140.76	0.43	60.53
Jelly	140.76	0.69	97.12
Precast Concrete Slab 100mm			
Sand	57.11	0.459	26.21
Jelly	57.11	0.88	50.14
KERB			
Sand	551	0.017	9.37
Jelly	551	0.032	17.63
GRANULAR SUB-BASE			
Jelly	120.45	1.00	120.45
wet mix macadam			
Jelly	172.43	1.00	172.43
Bituminous macadam			
Jelly	145.53	1.41	205.20
Bituminous Concrete			
Jelly	128.29	1.40	179.61

Sl	Items	Qty	Rate	Amount
1	Sand	137.70	138.00	19003.00
2	Jelly	923.06	126.00	116305.00
			Total	135308.00

Asst.Engineer
Dasarahalli Ward No 15

Asst.Executive Engineer
T.Dasarahalli Sub Division

Scanned with CamScanner